

1-5-2012

**Special Provision, Section 202 : Removing Structures and
Obstructions (Aluminum Bridge Rail), November 3, 2011,
Amended January 5, 2012**

Maine Department of Transportation

Follow this and additional works at: https://digitalmaine.com/mdot_docs

Recommended Citation

Maine Department of Transportation, "Special Provision, Section 202 : Removing Structures and
Obstructions (Aluminum Bridge Rail), November 3, 2011, Amended January 5, 2012" (2012).
Transportation Documents. 2377.
https://digitalmaine.com/mdot_docs/2377

This Text is brought to you for free and open access by the Transportation at Digital Maine. It has been accepted for inclusion in Transportation Documents by an authorized administrator of Digital Maine. For more information, please contact statedocs@maine.gov.

SPECIAL PROVISION
SECTION 202
REMOVING STRUCTURES AND OBSTRUCTIONS
(Aluminum Bridge Rail)

Description:

Aluminum bridge rail removed and not reused on the Project shall remain property of the Department. The Design-Builder shall use care during removal of the aluminum bridge rail so as not to damage the rail. The aluminum bridge rail, including both 2-bar and 4-bar rails, shall be removed by the Design-Builder as directed by the Resident and transported from the project site to the following location:

Maine Department of Transportation
576 US Route 1
Scarborough, ME

The Design-Builder shall contact the MaineDOT Region 1 office at (207) 885-7000 a minimum of 48 hours in advance of delivery of the aluminum bridge rail. The aluminum bridge rail shall be unloaded and placed by the Design-Builder as directed by the Department. The time of delivery shall be during weekday working hours when Department personnel are available to direct the unloading.

The aluminum rail shall be adequately secured to wooden pallets before being returned to the Department. Base plates, rail caps, splice bars, clamp bars and miscellaneous hardware shall be placed in wooden boxes on wooden pallets. The wooden boxes shall have wooden covers attached with two hinges and a clasp. The clasp shall be secured in the closed position by a method approved by the Resident. The size of the pallets and boxes shall be approved by the Resident. The weight limit on the pallets shall be such that no damage will occur to the pallets or the materials stored on the pallets.